

CERN Neutrino beam to Gran Sasso

Konrad Elsener, CERN



- **Overview of CNGS**
- **Expected performance / Challenges**
- **Cost / Schedule / Status**
- **Summary**

Overview




Aim: detect ν_τ **appearance** in a ν_μ beam sent from CERN to Gran Sasso (**732 km**)
→ **detect $\nu_\mu \rightarrow \nu_\tau$ oscillation**

Method:

- “classical” neutrino beam: protons on target
+ 2 horns to direct π^+ / K^+ towards Gran Sasso
- detector(s) at Gran Sasso: ν_τ detection efficiency + background suppression (ICARUS, OPERA)

Boundary Conditions:


- use existing accelerators and equipment, e.g. Items under construction for LHC...
in particular: SPS extraction towards T18→LHC
- ...but do not interfere with LHC !
- **no new surface building !!!**



CERN
Site de Préveessin

Prévessin-Moëns

LEP/LHC





proton
Pions/Kaons
TI 8


neutrinos ν_{μ}
to Gran Sasso


CERN
Site de Meyrin


Meyrin












S : Proton Synchrotron
 PS : Super Proton Synchrotron
 LHC : Large Hadron Collider

Overview (2)



Expected Performance



Proton beam performance

(based on SPS performance in 1997)

- > intensity in the SPS **4.8×10^{13}**

- > intensity per extraction **2.4×10^{13}** (10 μ s, 2 FE, $\Delta t = 50$ ms)

- > protons on target per year **4.5×10^{19}**
(SPS operation shared with other fixed target physics, testbeams,
LHC pilot or filling, machine development sessions, etc.)


"1 year": 200 days SPS operation, **55%** overall efficiency

SPS operational modes




CNGS cycle: 6 s (\Leftrightarrow 2 injections)

SPS operating for CNGS and standard fixed target physics (e.g. testbeams, experiments)



SPS operating for CNGS while filling LHC



Expected Performance (2)




Neutrino beam performance

No oscillation:

2450 ν_μ cc. events per kt per year

Assume $\sin^2(2\theta)=1$ and $\nu_\mu - \nu_\tau$ is the correct hypothesis:

$\Delta m^2 = 5 \times 10^{-3} \text{eV}^2$: **56** ν_τ cc. events
 $\Delta m^2 = 3 \times 10^{-3} \text{eV}^2$: **21** ν_τ per kt
 $\Delta m^2 = 1 \times 10^{-3} \text{eV}^2$: **2.3** ν_τ per year



-- Intermezzo --



CNGS project is still in an early phase ...

- ... based on calculations / simulations ...
- ... based on experience...(e.g. WANF - West Area neutrino facility)
- will present many ideas
- will show **few** approved technical designs
- **excellent moment for a workshop !**

A preliminary impression ...

To do ν_τ appearance experiment implies

- > maximize the neutrino beam intensity in E-“window”
- > “less problems” with beam stability / monitoring
- > “more problems” with detectors at Gran Sasso

Challenges



High intensity proton beam

- accelerator issues / beam transport / beam losses / monitoring / “routine” operation
(existing p accelerator chain + new CNGS proton beam-line)
- radiological issues

- **present** design: **4.8×10^{13} p circ. in SPS** (achieved in 1997)
- **future:** **7×10^{13} ??**
(due to investments made for SPS as LHC injector !)


- **3 fast extractions** per cycle instead of 2 (3 injections from PS to SPS) ??

Challenges (2)



Shielding: under study

Note the x,y scales!







Dose in the neutrino cavern

Heinz Vincke
CERN-TIS/RP

No iron roof





20 cm iron roof



Remark: annual dose in Gy per 4.5×10^{19} pot
 $7\text{m} < z < 10\text{m}$
 $z = 0\text{m} \dots$ target focal point

Dose in the wall of the neutrino cavern (4.5×10^{19} pot)

Averaged over the first 3 cm of the concrete



Challenges (3)



Target design

- thermo-mechanical shock
- heating / cooling
- handling / shielding

Note: very difficult already for present design values,
i.e. 2.4×10^{13} protons per fast extraction

→ **future: 3.5×10^{13} p per FE ??** 2 or 3 FE per cycle?

Challenges (4)



Horn + Reflector

→ **150 kA:**

- minimize material (ν_{μ} fluence!)
- fatigue issues
- handling / replacement

→ **future:**

180 kA ??

3 pulses instead of 2 ???

(cf. proton beam extraction)


→ sensitivities to horn / reflector alignment:

abandon motorization of horns ??

Challenges (5)



Decay tube and “Hadron Stopper”




B. Calcagno, 5 April 2000:

“worst case” scenario, 13.8×10^{19} p.o.t. / year

Two scenarios: Particle after 20 days of running and comparison between the maximum temperatures obtained with 1 and 2 cooling systems




LONGITUDINAL Temperature Profile related to the maximum temperatures in iron and in graphite



10 m

TEMPERATURE [°C]



COMPONENT	2 COOLING SYSTEM TEMP.MAX [°C]	1 COOLING SYSTEM TEMP.MAX [°C]
Graphite	194	298
Alu minu m	108	211
Cast-iron	137	256

Challenges (6)



Neutrino Beam Monitoring

- “hadron monitor” immediately after the target
(**secondary emission monitor**) ?
- “hadron monitor” upstream of the decay tunnel
(**ionisation chambers**) ?
- muon detection system - **silicon counters**: required absolute and relative accuracy ?

How much of this is really needed -
is “all protons are hitting the target” good enough ?

→ redundant fault detection system ...

Cost of the CNGS facility*


*without detectors at Gran Sasso



Civil Engineering (including decay tube)	41.6 MCHF
Equipment	19.6 MCHF
Infrastructure	7.3 MCHF
Contingency	2.5 MCHF
Total	71 MCHF
+ the value of recuperated equipment and investment for LHC: estimated 22 MCHF	

<u>Voluntary contributions announced:</u>	
Belgium	1 MCHF
France	1 MCHF
Germany	5 MCHF
Italy	47 MCHF
Comp. S. Paolo (Italy)	1.6 MCHF
Spain	4 MCHF
Total	59.6 MCHF
Switzerland	???.? MCHF

CNGS schedule / status



CNGS schedule / status



Approval of the CNGS facility by CERN Council:	December 1999
Civil engineering contract signed (within budget)	August 2000
Start civil engineering works	4 Sept. 2000
Presentation ICARUS and OPERA proposals	5 Sept. 2000
End civil engineering works	April 2003
Installation hadron stop / decay tube until...	June 2003
Installation general services until...	July 2004
Start equipment installation	July 2004
First beam to Gran Sasso	May 2005

Summary



- Following the approval of CNGS in Dec. 1999, construction has now started.
- First CNGS beam for the ν_τ appearance search is expected in May 2005.
- Work is under way to optimize many aspects of the CNGS facility.
- This workshop is an excellent opportunity to discuss our present ideas - thanks to the organizers and Fermilab !